

APR 8 1987

34

1 110052

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 119-20,757-0000
N/2 SE NE, SEC. 5, T 35 S, R 26 W/4E
3672 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8060

Lease Name Loyd Smith Well # 1-5

Operator: Zinke & Trumbo, Ltd.
Name & Address 111 West 5th, Suite 220
Tulsa, OK 74103

County Meade 204.75
Well Total Depth 6300 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1448

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Eagle Drilling, Inc. License Number 5380

Address Box 8609, Wichita, KS 67208

Company to plug at: Hour: 12:30 a.m. Day: 8 Month: 4 Year: 1987

Plugging proposal received from Keith Hill

(company name) Crown Consulting (phone) 316-624-0156

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2241'
Anhydrite 1223'

- 1st plug at base of surface pipe plus 30', with 40 sx cement,
- 2nd plug at 1/2 surface pipe with 40 sx cement,
- 3rd plug at 40-0' with 10 sx cement, 4th plug to circulate rathole with 15 sx cement,
- 5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by James Kapp (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5:30 a.m. Day: 8 Month: 4 Year: 1987

- ACTUAL PLUGGING REPORT
- 1st plug at 1470' with 50 sx cement,
 - 2nd plug at 800' with 40 sx cement,
 - 3rd plug at 40' with 10 sx cement,
 - 4th plug to circulate rathole with 15 sx cement,
 - 5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B. J. Williams.
(If additional description of operations necessary, use BACK of this form.)

INVOICED

APR 13 1987

DATE 4-15-87

Signed James Kapp (TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas

INV. NO. 16548

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date March 25, 1987 month day year

API Number 15-119-20,757-0000

OPERATOR: License # 8060 Name Zinke & Trumbo, Ltd. Address 111 W. 5th, Suite 220 City/State/Zip Tulsa, OK 74103 Contact Person Keith Hill Phone (316) 624-0156

1/2 SE NE Sec. 5 Twp. 35 S, Rg. 26 X West 3672 Ft. from South Line of Section 660 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5380 Name Eagle Drilling, Inc. City/State Wichita, KS 6727

Nearest lease or unit boundary line 660 feet County Meade Lease Name Loyd Smith Well # 1-5 Ground surface elevation 2238 feet MSL Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no Depth to bottom of fresh water 200' Depth to bottom of usable water 250' 350' Surface pipe by Alternate: 1 X 2 Surface pipe planned to be set 1500' Conductor pipe required 80' Projected Total Depth 6300' feet Formation Morrow/Chester

Well Drilled For: Well Class: Type Equipment: Oil SWD X Infield X Mud Rotary X Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

If OWWO: old well info as follows:

Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 03/19/87 Signature of Operator or Agent Title Agent

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 350 feet per Alt.

This Authorization Expires 9-20-87 Approved By 3-20-87

M602 3-27-87

850 - 1500 1448

SE NE Sec. 5 Twp. 35 S, Rg. 26 X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 1470' Base of Anhydrite 1530'-1430' feet depth with 50' sxs of 20/40 2nd plug @ 800' 800' feet depth with 50' sxs of 20/40 3rd plug @ 800'-930' 800' feet depth with 25' sxs of 20/40 4th plug @ 40'-0' feet depth with 10' sxs of 20/40 5th plug @ 15 feet depth with sxs of (2) Rathole with 15 sxs (b) Mousehole with 10 sxs

PUSHER Keith Hill TD 6300' FORMATION SURFACE PIPE 8 5/8 @ 1448' ANHYDRITE 223 ELEVATION 2241 STARTING TIME & DATE 12:30 AM COMPLETION TIME & DATE 5:30 AM 1st PLUG @ 1470 FT. W/ 50 SX 2nd PLUG @ 800 FT. W/ 40 SX 3rd PLUG @ 40' FT. W/ 10 SX 4th PLUG @ FT. W/ SX RAT HOLE CIRCULATED W/ 15 SX MOUSE HOLE CIRCULATED W/ 10 SX WATER WELL PLUGGED W/ No well CEMENT COMPANY B.J. Litan

TECHNICIAN 60/40 670 C&L RECEIVED STATE CORPORATION COMMISSION APR 1 1987 CONSERVATION DIVISION Wichita Kansas RECEIVED STATE CORPORATION COMMISSION APR 1 1987 CONSERVATION DIVISION WICHITA, KANSAS