

No. 1 **052041**  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202 **2-20**

API NUMBER 15-119-20,751-0000  
C NE SW, SEC. 4, T 35 S, R 26  EX  
1980 feet from S section line  
3300 feet from E section line  
Minnie C. Wyatt  
Lease Name Well 1-4

TECHNICIAN'S PLUGGING REPORT  
Operator License / 8060  
Operator: Zinke & Trumbo  
Name:  
Address 1202 E. 33rd; Ste. 100  
Tulsa, OK 74105

County Meade  
Well Total Depth 6300 **204.75** feet  
Conductor Pipe: Size 16" feet 80  
Surface Casing: Size 8 5/8" feet 1527

Abandoned Oil Well  Gas Well  Input Well  SMD Well  O&A   
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor J & S of Enid; Inc./Jerry Duncan Inc. License Number 8733  
Address P.O. Box 389, Enid, OK 73702

Company to plug at: Hour: \_\_\_\_\_ Day: 19 Month: 2 Year: 19 96

Plugging proposal received from Keith Hill  
(company name) Crown Consulting, Inc. (phone) 316-624-0156

Work: 4 1/2" at 6286' w/155 sx cement, PBD 6195', Perfs at 6002-6005', 6012-20'  
1st plug pump 1 sx hulls with 20 sx cement at 5800',  
2nd plug at 1550' with 50 sx cement, 3rd plug at 500' with 40 sx cement,  
4th plug at 40' with 10 sx cement. Drilling mud between plugs.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None  X  
Operations Completed: Hour: \_\_\_\_\_ Day: 20 Month: 2 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement, displaced with mud  
5800-6025',  
2nd plug loaded hole with mud, cut off casing at 2300', and pulled to 1550', Pumped 50 sx  
cement, displaced with mud from 1550-1420',  
3rd plug pulled casing to 500' and pumped 40 sx cement from 500-400',  
4th plug pulled casing to 40' and circulated 10 sx cement to surface.

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAY 21 1996

Remarks: Recovered 2300' of 4 1/2" casing. Used common cement by J & S.  
(If additional description is necessary, use BACK of this form.)  
I (XXXX) did not observe this plugging.

**INVOICED**  
DATE MAY 22 1996  
INV. NO. 45604

Signed Richard W. Lacey  
(TECHNICIAN)