

1 060965

6-2-87

API NUMBER 15-025-20,983-0000

C NW SW, SEC. 12, T 35 S, R 23 W/E

1980 feet from S section line

4620 feet from E section line

Lease Name Dunne Ranch Well # 1-12

County Clark

Well Total Depth 6000 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 802

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 9657

Operator: Quintana Petroleum Corporation
Name & Address 1050 17th Street, Suite 400
Denver, CO 80265

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company License Number 6033

Address 250 North Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 11 p.m. Day: 1 Month: 6 Year: 1987

Plugging proposal received from Ray Cane

(company name) Quintana Petroleum Corporation (phone) 303-628-9211

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1900' KB
Anhydrite 960'

1st plug at 960' with 60 sx cement,

2nd plug at 240' with 20 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1:30 a.m. Day: 2 Month: 6 Year: 1987

ACTUAL PLUGGING REPORT 1st plug at 960' with 60 sx cement,

2nd plug at 240' with 20 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

JUN 3 1987

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (operator or contractor) observe this plugging.

Signed Paul A. Luthi
(TECHNICIAN)

DATE 6-3-87

INV. NO. 17142 6-2

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date May 20 1987 month day year

API Number 15-025-20983-0000

OPERATOR: License # 9657 Name: QUINTANA PETROLEUM CORPORATION Address: 1050 - 17th Street, Suite 400 City/State/Zip: Denver, Colorado, 80265 Contact Person: E. Scott Kimbraugh Phone: (303) 628-9211

...C...NW...SW Sec. 12... Twp. 35... S, Rg. 23... X West 1980' Ft. from South Line of Section 4620' Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 660 feet County: Clark

CONTRACTOR: License # 5840 Name: Brand Drilling Co. City/State: Wichita, Kansas

Lease Name: DUNNE RANCH Well # 11-12 Ground surface elevation 1891 feet MSL

Well Drilled For: Oil SWD Infield X Mud Rotary X Gas Inj X Pool Ext Air Rotary OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no

If OWWO: old well info as follows:

Depth to bottom of fresh water 120' Depth to bottom of usable water 200'

Operator Well Name Comp Date Old Total Depth

Surface pipe by Alternate: 1 X 2 Surface pipe planned to be set 800'

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Conductor pipe required Projected Total Depth 5900 feet Formation: Morrow-Chester

Date 5/18/87 Signature of Operator or Agent Title: Production Technician

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt.

This Authorization Expires 11-20-87 Approved By 5-20-87

SPUD 5-21-87 8 5/8" 800' 20" 8 5/8"

NO WW

...C...NW...SW Sec. 12... Twp. 35... S, Rg. 23... X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 400'-200' feet depth with 50 sxs of 60/40 Poz. w/6% gel 50'-surface feet depth with 10 sxs of 60/40 Poz. w/6% gel 2nd plug @ 3rd plug @ 4th plug @ 5th plug @ (2) Rathole with 10 sxs (b) Mousehole with 10 sxs

PUSHER Ray Case TB 600 FORMATION Ball Run SURFACE PIPE 8 5/8" @ 802' ANHYDRITE 960' ELEVATION 1900' B STARTING TIME & DATE 6-1-87 11:00 PM COMPLETION TIME & DATE 6-2-87 1:30 AM 1st PLUG @ 560 FT. W/ 60 SX 2nd PLUG @ 240 FT. W/ 70 SX 3rd PLUG @ 40-0 FT. W/ 10 SX 4th PLUG @ FT. W/ SX RAT HOLE CIRCULATED W/ 15 SX MOUSE HOLE CIRCULATED W/ SX WATER WELL PLUGGED W/ SX CEMENT COMPANY B.G. TECHNICIAN Luthi 60/40 w/ 6% gel 90 on row JUN 3 - 1987 CONSERVATION DIVISION Wichita, Kansas