

TO: .
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-20084-00-01
Spot: SWNWNW Sec/Twnshp/Rge: 11-35S-23W
800 feet from N Section Line, 560 feet from W Section Line
Lease/Unit Name: DUNNE Well Number: 1OWW
County: CLARK Total Vertical Depth: 3547 feet

Operator License No.: 30705
Operator Name: YOUNGER ENERGY COMPANY
Address: 453 S. WEBB RD., STE 100
WICHITA, KS 67207

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 673 115.28
Production: Size 5.5 feet: 3547 WITH 100 SX CMT
Liner: Size _____ feet:

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/22/2000 3:00 PM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: TOM LARSON Company: YOUNGER ENERGY Phone: (316) 681-2542

Proposed Plugging Method: CIBP @ 3300'. 20 SX CMT ON BOTTOM & 200# HULLS. PUMP 50 SX CMT AT 700'. PUMP 10 SX CMT AT 40'.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 11/22/2000 5:30 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PERFS AT 3340-45. CIBP @ 3298' WITH 2 SX CMT ON TOP. 1ST PLUG SPOT 15 SX GEL & 50 SX CMT @ 700'. 2ND PLUG PULL TO 40' & CIRCULATE CMT TO SURFACE. STAYED FULL.

RECEIVED
STATE CORPORATION COMMISSION
NOV 30 2000
CONSERVATION DIVISION
Wichita, Kansas

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 2505' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed _____

INVOICED (TECHNICIAN)

DATE 12/1/00

NOV 27 2000

NOV 27 2000

20010610557D

Form 23