

8-215-129-10492-0000  
332

1 020393

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 19- E-11,602

C SW SW, SEC. 9, T. 34 S, R. 43

660 feet from S section line

4620 feet from E section line

Lease Name Interstate Unit Well # 6

County Morton 143.00

Well Total Depth 4400 feet

Conductor Pipe: Size feet

Surface Casing: Size 7 feet 1208

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Operator: Anadarko Petroleum Corp.

Name & Address P.O. Box 351

Liberal, KS 67905-0351

Abandoned Oil Well Gas Well Input Well X SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Serv. License Number 6547

Address 620 S. Lincoln, Liberal, KS 67901

Company to plug at: Hour: 9 a.m. Day: 20 Month: 8 Year: 19 91

Plugging proposal received from Don Horton

(company name) Sargent's (phone) 316-624-7455

Remarks: 4 1/2" at 4380' w/150 sx cement, PBTD 4380', Perfs at 4264-4309'

1st plug pump 1 sx hulls and 20 sx cement at perfs with tubing, load hole with mud,

2nd plug pump 50 sx cement at 1250',

3rd plug pump 30 sx cement at 650',

4th plug pump 10 sx cement at 40-0'

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 5 p.m. Day: 21 Month: 8 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement at perfs with

tubing, loaded hole with mud, plugs displaced with mud,

2nd plug pumped 50 sx cement at 1250',

3rd plug pumped 30 sx cement at 650',

4th plug at 33 to -4'.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 30 1991  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 1818' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED

DATE 9-12-91

INV. NO. 33097

Signed Glenn R Barlow (TECHNICIAN)