

15-129-10560-000094
11-13-87

1 061056

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name & Address: P.O. Box 351
Liberal, KS 67901

API NUMBER 15- Docket #E-11,602
C SE SE, SEC. 8, T 34 S, R 43 W/R
660 feet from S section line
660 feet from E section line
Lease Name Interstate Unit Well # 5
County Morton 143.33
Well Total Depth 4410 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 7 feet 1238

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address 620 South Lincoln, Liberal, KS 67901

Company to plug at: Hour: 8 a.m. Day: 10 Month: 11 Year: 19 87

Plugging proposal received from Doug Blair

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 4 1/2" at 4397' PRTD 4353' Perfs at 4309-13'

1st plug dump 2 sx hulls mixed w/gel followed by 30 sx common cement,

2nd plug spot 30 sx cement at casing cut, 3rd plug spot 40 sx cement from 1300-1125',

4th plug spot 40 sx cement from 650-450', 5th plug spot 10 sx cement from 50-0'.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5 p.m. Day: 13 Month: 11 Year: 1987

ACTUAL PLUGGING REPORT 1st plug pump 2 sx hulls and 30 sx common cement,

2nd plug pump 30 sx cement at 2200',

3rd plug pump 40 sx cement from 1300-1125',

4th plug pump 40 sx cement from 650-450',

5th plug pump 10 sx cement from 50-0', Heavy mud between each plug.

12-30-87
RECEIVED
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 2207' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

DATE 1-5-88

INV. NO. 19323

Signed Paul A. Luthi (TECHNICIAN)