

1 020082

6-10-87 15-129-10399-0000  
15-129-10399-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15 - Completion date 1/12/59  
C SW SW, SEC. 8, T 34 S, R 43 W/E  
660 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Interstate Unit Well # 2  
County Morton 142.16

Operator: Anadarko Petroleum Corporation  
Name & Address P.O. Box 351  
Liberal, KS 67901

Well Total Depth 4374 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1245

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address 620 South Lincoln, Liberal, KS 67901

Company to plug at: Hour: 3:30 p.m. Day: 8 Month: 6 Year: 19 87

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 5 1/2" at 4374' PBSD 4100' Perfs at 4302-4310'

1st plug set CIBP at 4100' with 20 sx cement on top through tubing,

2nd plug pump 30 sx cement at 2420', 3rd plug pump 40 sx cement at 1345',

4th plug pump 35 sx cement at 650-480', 5th plug pump 10 sx cement at 50-0'.

Plugging Proposal Received by Glenn Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10 a.m. Day: 10 Month: 6 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug CIBP at 4100' with 20 sx cement on top through tubing,

2nd plug pump 30 sx cement at 2420',

3rd plug pump 40 sx cement at 1345'-1145',

4th plug pump 35 sx cement at 650-480',

5th plug pump 10 sx cement at 50-0',

heavy mud between plugs.

Remarks: Used common cement by Sargent's. Recovered 2425' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED  
observe this plugging.

Formerly JM Huber Government "A" #6

Signed Glenn R Barlow  
(TECHNICIAN)

DATE 6-22-87

INV. NO. 17225

6-10

RECEIVED  
STATE CORPORATION COMMISSION

JUN 19 1987

CONSERVATION DIVISION  
Wichita, Kansas