

To: 1 020461  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Operator: Anadarko Petroleum Corporation  
Name & Address: P.O. Box 351  
Liberal, KS 67905-0351

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address 620 S. Lincoln, Liberal, KS 67901

Company to plug at: Hour: 2:30 p.m. Day: 30 Month: 4 Year: 19 92

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

work: 5 1/2" at 4384' w/150 sx cement, PBSD 4350', Perfs at 4312-25'

1st plug pump 1 sx hulls and 15 sx cement at perfs with tubing and packer,

2nd plug pull tubing, load hole, shoot pipe off at 2233', pump 25 sx cement at 2200',

3rd plug pump 40 sx cement at 1280', 4th plug pump 30 sx cement at 650',

5th plug pump 10 sx cement at 40 to -4'.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 4:30 p.m. Day: 4 Month: 5 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 15 sx cement at perfs w/tubing & packer,

2nd plug pulled tubing, loaded hole, and shot pipe off at 2233'. Pumped 25 sx cement at 2200',

3rd plug pumped 40 sx cement at 1280',

4th plug pumped 30 sx cement at 650',

5th plug pumped 10 sx cement at 40 to -4'.

Remarks: Used common cement by Sargent's. Recovered 2233' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

(and/or witness) observe this plugging.

INVOICED  
DATE MAY 21 1992  
INV. NO. 35297

15-129-10394-00083R

API NUMBER 15- Drilled 9/20/57

NE SW, SEC. 8, T. 34 S, R. 43 W/EX

1980 feet from S section line

3300 feet from E section line

Lease Name Interstate Unit Well # 3

County Morton 142.51

Well Total Depth 4385 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1251

RECEIVED  
CORPORATION COMMISSION  
MAY 21 1992  
CONSERVATION DIVISION  
WICHITA, KANSAS  
FORM CP-213  
Rev. 01-84

Signed Glenn R. Barlow (TECHNICIAN)