

To: 1 100115 4-16
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- Spud date 11/3/65
App. C SE, SEC. 8, T 34 S, R 43 W/E
1451 feet from S section line
1463 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License / 4549
Operator: Anadarko Petroleum Corporation
Name:
Address: P.O. Box 351
Liberal, KS 67905-0351

Lease Name Smith "B" Well # 4
County Morton 43.71
Well Total Depth 1345 feet
Conductor Pipe: Size feet
Surface Casing: Size none feet

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargents Casing Pulling Service License Number 6547
Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 12:30 p.m. Day: 16 Month: 4 Year: 19 97

Plugging proposal received from Kirby Lillard
(company name) Sargents Casing Pulling Service (phone) 316-624-7455

were: 7" at 1300' w/450 sx cement, Open hole
1st plug pump 2 sx hulls and 32 sx cement through tubing from 1345-1245',
2nd plug pull to 610' and spot 32 sx cement,
3rd plug pull to 40' and spot 12 sx cement.

RECEIVED
KANSAS CORPORATION
1997 APR 22 15

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 p.m. Day: 16 Month: 4 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug ran tubing to 1300', loaded hole with mud, and pumped 32 sx cement with 2 sx hulls and displaced to 1300-1200',
2nd plug pulled to 330' and spotted 32 sx cement from 610-510', displaced with mud,
3rd plug pulled to 40' and spotted 12 sx cement from 40-0'.

Remarks: Used common cement by Sargents. No casing recovery.
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED
DATE 4-28-97

Signed *Long Winter* (TECHNICIAN)

INV. NO. 48003
4-16 JUN 17 1997