

1 110090

NOV 10 1987

15-129-10561-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Drill completion 1/11/58

C SW SE, SEC. 8, T 34 S, R 43 W/E  
660 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Interstate Unit Well # 4

Operator: Anadarko Petroleum Corporation

County Morton 143.13

Name & Address P.O. Box 351

Well Total Depth 4404 feet

Liberal, KS 67901

Conductor Pipe: Size feet

Surface Casing: Size 7' feet 1256

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address 620 South Lincoln, Liberal, KS 67901

Company to plug at: Hour: 1:30 p.m. Day: 5 Month: 11 Year: 19 87

Plugging proposal received from Doug Blair

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 4 1/2" at 4404 PBD 4100'w/CIBP Perfs at 4324-40' Elevation 3614.35'

1st plug CIBP with 20 sx cement on top,

2nd plug pump 30' sx cement at cut off, 3rd plug pump 40 sx cement at 1325-1175',

4th plug pump 35 sx cement at 650-480', 5th plug pump 10 sx cement at 50-0'. Heavy mud between all plugs.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 1 p.m. Day: 10 Month: 11 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4100' with 20 sx cement on top,

2nd plug at 2009' with 30 sx cement,

3rd plug at 1425' with 40 sx cement,

4th plug at 650' with 35 sx cement,

5th plug at 50-10' with 10 sx cement.

RECEIVED STATE CORPORATION COMMISSION

NOV 16 1987

11-16-87

CONSERVATION DIVISION Wichita Kansas

Remarks: Used common cement by Sargent's. Recovered 2009' of 4 1/2" casing. (if additional description is necessary, use BACK of this form.)

Observe this plugging.

DATE NOV 20 1987

Signed James R. Kay (TECHNICIAN)

INV. NO. 18897