

To: 020637 1-6
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-129-20,406-0000 1148
NW NW SE NE, SEC. 7, T 34 S, R 43 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5156
Operator: Edger W. White
Name & Address 701 Vilymaca St.
Elkhart, KS 67950

3890 feet from S section line
1250 feet from E section line
Lease Name Interstate Red ^{Cave} Well # 5
County Morton 47.45
Well Total Depth 1460 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 473

Abandoned Oil Well Gas Well X Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547
Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 11 a.m. Day: 4 Month: 1 Year: 1993

Plugging proposal received from Doug Blair
(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 4 1/2" at 1458' w/275 sx cement, Perfs at 1401-04, 1408-16'
1st plug pump 1 sx hulls and 20 sx cement at 1406' with tubing,
2nd plug pump 30 sx cement at 500-180'. Check backside.
3rd plug pump 5 sx cement at 40 to -4'.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 6:30 p.m. Day: 6 Month: 1 Year: 1993

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement at 1406' with tubing,
2nd plug pumped 30 sx cement at 500-180'. Checked backside.
3rd plug pumped 5 sx cement at 40 to -4'.

Remarks: Used common cement by Sargent's. No casing recovery.

INVOICED
(If additional description is necessary, use BACK of this form)
I (did / ~~did not~~) observe this plugging.

DATE FEB 16 1993
INV. NO. 37333

STATION COMMISSION
JAN 13 1993
CON. DIVISION
WICHITA, KANSAS
Signed Glenn R. Barlow
(TECHNICIAN)