

1 050762

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 129-20,795 - 0000

NW SW SW, SEC. 5, T 34 S, R 43 W/E

990 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5254

Lease Name Williams Well # 1

Operator: Midco Exploration, Inc.  
Name & Address 200 E. 1st St., Suite 411  
Wichita, KS 67202

County: Morton 157.63

Well Total Depth 4850 Mississippi feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1404

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Mustang Drilling & Exploration, Inc. License Number 5652

Address P. O. Box 1609, Great Bend, KS 67530

Company to plug at: Hour: 4:00 pm Day: 11 Month: February Year: 19 86

Plugging proposal received from Bill Nelson

(company name) Mustang (phone) 316-792-7323

were: to fill hole with heavy mud and spot cement through drill pipe Elevation N/A  
Anhydrite 1398-1404'

1st plug 30' below the base of the surface pipe with 50 sx cement

2nd plug at 700' with 40 sx cement  
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rathole with 15 sx cement

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 7:00 pm Day: 11 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1430' with 50 sx cement, 2nd plug at 700' with 40  
sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface  
with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

FEB 17 1986

Remarks: Used 60/40 Pozmix 6% gel by Dowell.

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED

(did not) observe this plugging.

DATE 1-17-86

Signed Richard W. Lacey  
(TECHNICIAN)

INV. NO. 12631

2-11

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 2 1 1986 month day year

API Number 15- 129-20,795-0000

OPERATOR: License # 5254 Name Midco Exploration, Inc. Address 200 E. 1st. St. - Suite 411 City/State/Zip Wichita, Ks. 67202 Contact Person Harvey Gough Phone 316-267-3613

NW SW SW Sec. 5 Twp. 34S S. Rg. 43 East West 990 4950 Ft. from South Line of Section Ft. from East Line of Section (Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5652 Name Mustang Drilling City/State Great Bend, Ks. 67530

Nearest lease or unit boundary line 330 feet County Morton Lease Name Williams Well # 1 Ground surface elevation Unknown feet MSL Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no Surface pipe by Alternate: 1 X 2 Depth to bottom of fresh water 200 Depth to bottom of usable water 300 Surface pipe planned to be set 1400' Projected Total Depth 4850 feet Formation Mississippian

Well Drilled For: Well Class: Type Equipment: Oil SWD Infield X Mud Rotary X Gas Inj X Pool Ext. Air Rotary OWWO Expl Wildcat Cable

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging Hole to KCC specifications. cementing will be done immediately upon setting production casing. Date Jan. 29, 1986 Signature of Operator or Agent Harvey Gough Title Vice President

For KCC Use: Conductor Pipe Required feet: Minimum Surface Pipe Required 350 feet per Alt. This Authorization Expires 7-29-86 Approved By 1-29-86 SET 1400' of 6 3/8" on 1/31/86

PUSHER Bill Nelson TD 4850' FORMATION MISS SURFACE PIPE 1404 @ 8 5/8" ANHYDRITE 1398' - 1404' ELEVATION N/A STARTING TIME & DATE 4:00pm 2/11/86 COMPLETION TIME & DATE 7:00pm 2/11/86 1st PLUG @ Surface FT. W/ 50 SX 1430 2nd PLUG @ 700 FT. W/ 40 SX 700 3rd PLUG @ 40 FT. W/ 50 SX 40 4th PLUG @ FT. W/ SX RAT HOLE CIRCULATED W/ 15 SX MOUSE HOLE CIRCULATED W/ SX WATER WELL PLUGGED W/ SX CEMENT COMPANY Penwell TECHNICIANacey

RECEIVED STATE CORPORATION COMMISSION FEB 17 1986 CONSERVATION DIVISION Wichita, Kansas