

12-28

To: 1 020199
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 129-20,909-0000

SE NW, SEC. 35, T 34 S, R 43 W/E

4030 feet from S section line

4030 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3558

Lease Name St. Joan of Arc Well # 35-11

Operator: Tom Brown, Inc.

County Morton 152.10

Name & Address P.O. Box 2608

Well Total Depth 4680 feet

Midland, TX 79702

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1497

Abandoned Oil Well Gas Well RECEIVED Well SWD Well D&A

Other well as hereinafter indicated STATE CORPORATION COMMISSION

Plugging Contractor Tom Brown, Inc. License Number 3558

Address P.O. Box 2608, Midland, TX 79702

Company to plug at: Hour: 11 a.m. Day: 12 Month: 12 Year: 19 88

Plugging proposal received from Norman Clark

(company name) Tom Brown, Inc. (phone) 915-682-9944

were: 4 1/2" at 3132' PBSD 3132' Perfs at 2850-66', 3046'-bottom perf

Retrievable bridge plug left in hole at 2894 w/10.5 yards on top

1st plug set CIBP at 2800' with 2 sx cement on top,

2nd plug pump 50 sx cement at 1547-1350',

3rd plug pump 20 sx cement at 745-665', 4th plug pump 10 sx cement at 40-0'.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 3:45 p.m. Day: 28 Month: 12 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2800' with 2 sx cement on top, pulled 4 1/2" out, ran tubing,

2nd plug pumped 50 sx cement at 1547-1350',

3rd plug pumped 20 sx cement at 745-665',

4th plug pumped 10 sx cement at 60-0'.

Remarks: Used Class H cement by Halliburton. Recovered 2305' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

(did / observe this plugging.

DATE 1-11-89

INV. NO. 23613

Signed Glenn Barlow (TECHNICIAN)