

To: 1 100192 1-26
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-129-20,637-0002

TECHNICIAN'S PLUGGING REPORT
Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name & Address P.O. Box 351
Liberal, KS 67905-0351

NW NW SE SE, SEC. 34, T 34 S, R 43 W ~~XX~~
1250 feet from S section line
1250 feet from E section line
Lease Name Leewe A Well # I
County Morton 103.51
Well Total Depth 3185 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 704

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 12:30 p.m. Day: 26 Month: 1 Year: 19 98

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

were: 4 1/2" at 3184' w/550 sx cement, PBTD 2830', Perfs at 2807-10, 2821-25, 2585-94'
1st plug set CIBP at 2770', 2nd plug pump 20 sx cement with 2 sx hulls from 2584-2384',
3rd plug pump 65 sx cement from 700-0'.

Plugging Proposal Received by Gary Winters
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 p.m. Day: 26 Month: 1 Year: 19 98

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2770',
2nd plug pumped 2 sx hulls and 20 sx cement from 2584-2384',
3rd plug pumped 65 sx cement from 700-0'.
Cement stopped at 65' below surface. Pressured up back to 150 psi with 15 sx cement.

Remarks: Used common cement by Sargent & Horton. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED

I (did / ~~did not~~) observe this plugging.

DATE 2-9-98

Signed Gary Winters
(TECHNICIAN)

INV. NO. 50039