

1100365

TO: STATE CORPORATION COMMISSION

API NUMBER 15-129-00439 - 0000
SW SEC. 33, T 34 S, R 43 W

CONSERVATION DIVISION - PLUGGING SECTION 3960 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1297 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME LINSOTT WELL # 2-33

TECHNICIAN'S PLUGGING REPORT 6/20 COUNTY MORTON 96.20

OPERATOR LICENSE # 4549 WELL TOTAL DEPTH 2960 FEET

OPERATOR: ANADARKO PETROLEUM CORP. PRODUCTION CSG: SIZE 4 1/2" @ 2958' WITH 125 SX

NAME AND PO BOX 351 SURFACE CASING: SIZE 7" @ 669' WITH 175 SX

ADDRESS LIBERAL, KS 67905-0351

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING LICENSE NUMBER 31151

ADDRESS RT 1 BOX 49 BA TYRONE, OK 73951

COMPANY TO PLUG AT: HOUR: 3:00 PM DAY: 20 MONTH: 06 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM DON HORTON

(COMPANY NAME) SARGENT & HORTON PLUGGING (PHONE) 316-624-7455

WERE: PERFS AT 2824-2885

1ST PLUG SPOT 20 SX CEMENT WITH 2 SX HULLS AT 2824-2624. 2ND PLUG SPOT 20 SX CEMENT AT 1600' INSIDE CASING. 3RD PLUG SPOT 40 SX CEMENT AT 700'. 4TH PLUG SPOT 10 SX CEMENT AT 40' TO 0'.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 11:00 PM DAY: 20 MONTH: 06 YEAR: 2000

ACTUAL PLUGGING REPORT

1ST PLUG SPOT 20 SX CEMENT AND 2 SX HULLS AT 2824-2624. 2ND PLUG SPOT 20 SX CEMENT AT 1600' INSIDE CASING. 3RD PLUG SPOT 40 SX CEMENT AT 700'. 4TH PLUG SPOT 10 SX CEMENT AT 40' TO 0'.

RECEIVED STATE CORPORATION COMMISSION

JUN 22 2000

REMARKS: USED COMMON CEMENT BY SARGENTS. RECOVERED 720' OF 4 1/2" CASING. (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.) CONSERVATION DIVISION Wichita, Kansas

I (DID) OBSERVE THIS PLUGGING.

INVOICED SIGNED Gary Winters (TECHNICIAN) FORM CP-2/3
DATE 6/27/00 INV. NO. 61896

AWY