

1 020078

5-29-87 15-129-10453-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill completion 6/6/55

NE SW NW, SEC. 32, T 34 S, R 43 W/E

3630 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Interstate Unit Well # 74

Operator: Anadarko Petroleum Corporation
Name &

County: Morton 148.62

Address P.O. Box 351
Liberal, KS 67901

Well Total Depth 4573 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1247

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address 620 South Lincoln, Liberal, KS 67901

Company to plug at: Hour: 10 a.m. Day: 28 Month: 5 Year: 19 87

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 5 1/2" at 4572.5 PBTD 4100' Perfs at 4203-4216'

1st plug CIBP at 4100' with 20 sx common cement on top.

2nd plug load hole with heavy mud and pump 50 sx cement at 1350-1150',

3rd plug pump 35 sx cement at 650-480',

4th plug pumped 10 sx cement at 40'.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:15 p.m. Day: 29 Month: 5 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4100' with 20 sx cement,

2nd plug loaded hole with heavy mud and pumped 50 sx cement at 1350-1150',

3rd plug pumped 35 sx cement at 650-480',

4th plug pumped 10 sx cement at 40'.

JUN 3 - 1987

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 1364' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

Signed Glenn R. Barlow
(TECHNICIAN)

DATE 6-3-87

INV. NO. 17136

JUN 29 1987