

6-20 15-129-30066-0000  
96 R

1 020234

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Docket #E-11,602

SE SE NW, SEC. 32, T 34 S, R 43 W/E

2740 feet from S section line

3090 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Interstate Unit Well # 78

Operator: Anadarko Petroleum Corporation  
Name

County Morton 139.43

Address P.O. Box 351

Well Total Depth 4290 feet

Liberal, KS 67905-0351

Conductor Pipe: Size feet

Surface Casing: Size 7 feet 1229

Abandoned Oil Well Gas Well Input Well X SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address 620 South Lincoln, Liberal, KS 67901

Company to plug at: Hour: 3:30 p.m. Day: 16 Month: 6 Year: 1989

Plugging proposal received from Doug Blair

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 3 1/2" at 4268' PBTD 4100' Perfs at 4190-4222' Elevation 3541' GL

1st plug 15 sx cement on CIBP at 4100',

2nd plug at freepoint with 25 sx cement,

3rd plug spot 30 sx cement at 1260-1160', 4th plug spot 25 sx cement at 500-400',

5th plug pump 15 sx at 80'.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 2 p.m. Day: 20 Month: 6 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4100', ran tubing, pumped 15 sx on top,

2nd plug ran 25 sx cement at 2256', heavy mud between plugs,

RECEIVED  
STATE CORPORATION COMMISSION

3rd plug pumped 37 sx cement at 1260',

JUN 26 1989 6-26-89

4th plug pumped 25 sx cement at 500',

CONSERVATION DIVISION  
Wichita, Kansas

5th plug pumped 15 sx cement at 80'.

Remarks: Used common cement by Sargent's. Recovered 2256' of 3 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

DO NOT REMOVE observe this plugging.

Signed Glenn R. Egan (TECHNICIAN)

DATE 6-27-89

INV. NO. 25123

6-20