

1 020077

5-27-87 15429-10451-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drill completion 4/11/55
C NE NW, SEC. 32, T 34 S, R 43 W/E
4620 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Interstate Unit Well # 72

Operator: Anadarko Petroleum Corporation
Name &

County Morton 149.01

Address P.O. Box 351

Well Total Depth 4585 feet

Liberal, KS 67901

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1253

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address 620 South Lincoln, Liberal, KS 67901

Company to plug at: Hour: 1:30 p.m. Day: 22 Month: 5 Year: 19 87

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 5 1/2" at 4585' PBTD 4100' Perfs at 4213-42'

1st plug on stub with 30 sx cement,

2nd plug at 1300' with 40 sx cement,

3rd plug at 650' with 35 sx cement,

4th plug at 40-0' with 10 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:40 a.m. Day: 27 Month: 5 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug CIBP at 4100' with 20 sx cement on top,

2nd plug pumped 30 sx cement at 2400',

3rd plug pumped 40 sx cement at 1350-1150',

4th plug pumped 35 sx cement at 650-480',

5th plug pumped 10 sx cement at 50-0'.

JUN 3 1987

Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 2408' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
Please observe this plugging.

DATE 6-3-87

Signed Glen R. Barber
(TECHNICIAN)

INV. NO. 17137

5-27 JUN 29 1987