

1 020777

7-12

15-129-30065-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Spud date 10/12/65

S/2 S/2 SW NW, SEC. 32, T 34 S, R 43 W/4  
2710 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Interstate Unit Well # 77

Operator: Anadarko Petroleum Corporation

County Morton

Name & Address P.O. Box 351

Well Total Depth 4285 139.26 feet

Liberal, KS 67905-0351

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 37 feet 1203

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent & Horton Plugging Inc. License Number 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 11 a.m. Day: 11 Month: 7 Year: 19 94

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging Inc. (phone) 405-854-6515

Wells: 3 1/2" at 4283' w/100 sx cement, PBD 4215', Perfs at 4180-84, 4187-96'

1st plug CIBP at 4110', run tubing and put 10 sx cement on top of CIBP, load hole with mud,

2nd plug pump 45 sx cement at 1235',

3rd plug pump 25 sx cement at 650',

4th plug fill with cement from 40' to -4'.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:15 p.m. Day: 12 Month: 7 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug CIBP set at 4110, ran tubing and put 10 sx cement on top of CIBP, loaded hole with mud,

2nd plug pumped 45 sx cement at 1235',

3rd plug pumped 25 sx cement at 650',

4th plug filled with cement 40 to -4'.

Remarks: Used common cement by Sargent & Horton's. Recovered 1235' of 3 1/2" casing  
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE JUL 20 1994

INV. NO. 40833

7-12

Signed Glenn R Barlow (TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 15 1994  
CONSERVATION DIVISION  
Wichita, Kansas