

WELL PLUGGING RECORD

15-175-20664-00-00

Give All Information Completely
Make Required Affidavit

COUNTY Seward SEC. 23 TWP. 34 RGE. 32W E/W
Location as in quarters or footage from lines:
C SE NW

	⊕		

Lease Owner Par Petroleum, Inc.
Lease Name Adeline Davies Well No. 1-23
Office Address Box 280 Liberal, Kansas 67901
Character of Well (Completed as Oil, Gas or Dry Hole): Dry
Date Well Completed 3-1-83
Application for plugging filed 6-22-84
Plugging commenced 7-24-84
Plugging completed 7-26-84
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi

Producing formation _____ Depth to top _____ bottom _____ T.D. 6550

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	1528	none
				4 1/2	6350	2726

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Pump 15 sks. of cement @ 4518 to 4400
Pump 50 sks. of cement @ 1578 to 1478
Pump 35 sks. of cement @ 700 to 600
Put 10 sks. of cement @ 40 to 0

Cut off & cap 8 5/8 3' below ground level

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargents Casing Pulling Service Box 506 Liberal, Kansas 67901

STATE OF Kansas COUNTY OF Seward, ss.
Ralph M. Reynolds (~~employee xxx xxx xxx~~) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.


(Signature) Ralph M. Reynolds
Liberal Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of August, 19 84

Marjorie A. Kennedy
Marjorie A. Kennedy Notary Public

My Commission expires: 1-8-88

RECEIVED
STATE CORPORATION COMMISSION



AUG 06 1984

CONSERVATION DIVISION
Wichita, Kansas

15-175-20664-00-00

DRILLER'S LOG

Quinque Operating Company
18 W. Third St., Box F
Liberal, Kansas 67901

Adeline-Davies #1-23
SE/NW of Sec.23-34S-32W
Seward Co., Ks.

Surface Casing: Ran 38 jnts. of new 24#
8 5/8", 1530-69T, Set @ 1530 KB. Cement
with 500 sks. lite, 2% CC. Held with 200
sks. of Class H-3%, Flow held with 1000#
Plugged down @ 7:30 pm, 11/15/82.
Halliburton did cementing.

Commenced: 11/25/82
Completed: 12/11/82

Total Depth: 6550'

FORMATION	FROM	TO	REMARKS
Surface sand	0'	373'	LTD: 6538'
Red Bed	373'	1450'	
Under surface	1450'	2163'	
Lime & Shale	2163'	6550'	

RECEIVED
STATE CORPORATION COMMISSION
JUN 21 1984
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the log on the above captioned well to the best of my knowledge.

NRG Drilling, Inc.

By Elmer Jack Taylor
Elmer Jack Taylor
Vice-President

Subscribed and sworn to before me this 15 day of December 19 82

STATE NOTARY PUBLIC
MARRNELL PRIBBLE
Seward County, Kansas
My Appt Expires 8-20-83

Marrnell Pribble
Marrnell Pribble

My commission expires: 8-20-83