

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-175-20,781-00-00

LEASE NAME DAVIES

WELL NUMBER 1-23

SPOT LOCATION SW SW

SEC. 23 TWP. 34S RGE. 32 ~~xxx~~ or (W)

COUNTY Seward

Date Well Completed 8/25/85

Plugging Commenced 8/22/85

Plugging Completed 8/25/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Donald C. Slawson

ADDRESS Suite 700, 20 N. Broadway, Okla. City, OK 73102

PHONE # (405) 232-0201 OPERATORS LICENSE NO. 5181

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filled? attached If not, is well log attached? _____

Producing formation none Depth to top _____ bottom T.D.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	1,558'	none
				4-1/2"	4,778'	3,023'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Shot casing @ 3,023'. Worked pipe free. TOH to 2,600'. Spot 50 sx cement plug 2,600' - 2,500'. Displace hole w/9.0 ppg mud. TOH to 1,550'. Spot 50 sx cement plug 1,550' - 1,450'. TOH to 800'. Spot 50' sx plug 800' - 700'. TOH. Spot 10 sx cement plug 3' - 40'. Cut off surface casing & weld on cap.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547
Address 620 S. Lincoln, Liberal, KS 67901

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Daniel G. Wilson

(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Daniel G. Wilson

(Address) Suite 700, 20 N. Broadway

Oklahoma City, OK 73102

SUBSCRIBED AND SWORN TO before me this 10th day of September, 1985

STATE CORPORATION COMMISSION

Berna J. Hawthorne
Notary Public

My Commission expires: 5/7/88

SEP 12 1985

9-12-85

CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 01-84