

15-189-20008 00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Stevens County, Sec. 24 Twp. 34S Rge. (E) 37 (W)

Location as "NE/CNW%SW%" or footage from lines 145' W & 55' N of CL NE NE

Lease Owner Mobil Oil Corporation

Lease Name Albert Peachy #1 Well No. 1

Office Address P.O. Box 1828, Oklahoma City, Oklahoma 73101

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed September 22 19 67

Application for plugging filed Attached 19 67

Application for plugging approved September 26 19 67


Plugging commenced September 22 19 67

Plugging completed September 22 19 67

Reason for abandonment of well or producing formation Drilled Dry

If a producing well is abandoned, date of last production - 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eddie Eaves  
Producing formation - Depth to top - Bottom - Total Depth of Well 6927' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Drilled Dry				8-5/8"	1768"	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Cement plug set in casing with 40 sacks of cement at 700'. Came up to 600'. Set 20 sacks of cement from 45' to surface.

Stamp: CONSERVATION DIVISION, WICHITA, KANSAS, OCT 19 1967

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graham-Michaelis Drilling, Inc.  
Address 211 N. Broadway, Wichita, Kansas 67202

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.  
Paul K. Langenberg (employee of owner) or (owner or operator) of the above-described well; being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul K. Langenberg  
P.O. Box 1828, Oklahoma City, Oklahoma 73101  
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of October, 19 67

My commission expires 9-8-71

Murline Sanders  
Notary Public.

PEACHEY UNIT NO. 2

*Albert Peachey #1*

WELL RECORD:

LOCATION:

NE NE Section 24-34-37  
Stevens County, Kansas

Commenced: 9-5-67  
Completed: 9-22-67  
(Rotary)

CONTRACTOR:

Graham-Michaelis Drilling, Inc.  
Liberal Division  
P. O. Box 1294  
Liberal, Kansas 67901

CASING RECORD:

55 Joints 8-5/8" 24# Casing Set  
at 1760' - Cemented w/425 sx 12%  
Gel 2% cc and w/100 sx Common  
2% cc


LOG

Clay & Sand	0 - 169
Sand & Red Bed	169 - 1092
Red Bed	1092 - 1761
Shale	1761 - 2952
Lime & Shale	2952 - 5298
Lime	5298 - 5410
Lime & Shale	5410 - 5700
Shale	5700 - 5910
Lime & Shale	5910 - 6042
Shale	6042 - 6418
Lime & Shale	6418 - 6548
Lime	6548 - 6898
Lime & Chert	6898 - 6927

6927' - Total Rotary Depth

The undersigned, Graham-Michaelis Drilling, Inc., Liberal Division, certifies that the above log is a true and correct copy of the formations encountered in drilling the above mentioned well, as taken from the Daily Drilling Report.

GRAHAM-MICHAELIS DRILLING, INC.  
LIBERAL DIVISION

By   
H. R. Michaelis

HRM/rw

RECEIVED  
STATE CORPORATION COMMISSION

OCT 19 1967

CONSERVATION DIVISION  
WICHITA, KANSAS