

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-189-10054-
LEASE NAME Reacky #1 Unit
WELL NUMBER 2

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

1980 Ft. from N Section Line
1982 Ft. from E Section Line
SEC. 24 TWP. 34 RGE. 37 (E) or (W)
COUNTY Stevens
Date Well Completed 5-20-99
Plugging Commenced 4-12-99
Plugging Completed 4-13-99

LEASE OPERATOR Mobil Oil Corporation
ADDRESS Box 2173 Liberal KS 67905-2173
PHONE# (316) 626-1142 OPERATORS LICENSE NO. 5208

Character of Well Gas
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-12-99 (date)
by Gary Winters (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? On file with KCC
Producing Formation Chase Depth to Top 2672 Bottom 2810 T.D. 6980

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				<u>8 3/8</u>	<u>1753</u>	<u>-</u>
				<u>5 1/2</u>	<u>6844</u>	<u>1925</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Mixed 3 SX hulls to 25 SX cmt. to plug perfs. from 6328 to 6128. Tag plug @ 6100. Recover 1925. Pulled to 1780. Circ. w/mud 50 SX 1780 to 1630. 40 SX 700 to 600 10 SX 40 to 0 Cut off & cap 8 3/8 4 ft. below G.L.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent And Horton Plugging Inc. License No. 31151
Address Rt 1 Box 49 BA Tyrone OK 73951-9731


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mobil Oil Corp.

STATE OF Kansas COUNTY OF Seward, ss.

Sharon A. Cook (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Sharon A. Cook

(Address) P.O. Box 2173 Liberal KS 67905



STATE OF KANSAS CORPORATION COMMISSION RECEIVED AND SWORN TO before me this 26th day of April, 19 99

Lynda K. Hunt Notary Public

APR 30 My Commission Expires: February 20, 2001