

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.  
3-7-96  
1996 MAR -7 A 11:24

LEASE NAME Baalman

WELL NUMBER #1

4950 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 1 TWP. 11 RGE. 31 (E) or (W)

COUNTY Gove

Date Well Completed 2-15-86

Plugging Commenced 12-16-95

Plugging Completed 12-16-95

LEASE OPERATOR Prairie Drilling, Inc.

ADDRESS P.O. Box 203, Hays, KS 67601

PHONE#(913) 628-2812 OPERATORS LICENSE NO. 31446

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-15-95 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? Yes

Producing Formation Lansing KC, Marmaton Depth to Top 4011 Bottom 4596 T.D. 4651  
Fort Scott

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Dakota 1292-1464	Water	0	217	8 5/8	215	0
Lansing 4010-4290	Oil & Water	0	4643	4 1/2	4643	0
Cherokee 4472-4600	Oil & Water					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from 0 feet to 4600 feet each set. Perforate casing @ 185'. Pump 20 sks. cement down back side. 300# standing pressure. Pump 180 sacks cement with 500 sks hulls down 4 1/2" casing followed by 200 sks cement with 500# hulls down casing. Max pressure 400#. Shut in 200#.

Name of Plugging Contractor Allied Cementing License No. NA

Address P.O. Box 31, Russel, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Prairie Drilling Co.

STATE OF Kansas COUNTY OF Ellis, ss.

R. L Finnesy (Employee of Operator) or (Operator) o

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. L Finnesy

(Address) 312 Skyline Court, Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 4th day of March, 19 96

Cheryl Finnesy  
Notary Public

My Commission Expires: 6-24-96

