

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-063-20,340-00-00

LEASE NAME Coberly NN

WELL NUMBER # 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

2970 Ft. from S Section Line

4950 Ft. from E Section Line

LEASE OPERATOR Vintage Petroleum, Inc.

SEC. 17 TWP. 14S RGE. 28 E(E) or (W)

ADDRESS 4200 One Williams Center Tulsa, OK 74172

COUNTY Gove

PHONE#(918) 592-0101 OPERATORS LICENSE NO. 03122

Date Well Completed 4-15-77

Character of Well Oil

Plugging Commenced 8-10-93

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8-15-93

The plugging proposal was approved on June 7, 1993 (date)

by Marion Schmidt (KCC District Agent's Name).

is ACO-1 filed? Yes If not, is well log attached? No

Producing Formation Pawnee Depth to Top 4204 Bottom 4208 T.D. 4280

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Pawnee	Oil, Gas, Water	Surf	411	8 5/8	411	0
		Surf	4279	4 1/2	4279	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set
Perforated 4 1/2" csg with 4 SPF @ 2114 X 1148', RTH w/ 2/38 TBG to 4009'
Mix & pump 100 sx 60/40 PD2- from 4009' to 2200'
With TBG @ 2000', pumped 125 sx 60/40 Pox from 2000' to surface.
Pumped 75 sx 66/40 Pox down 8 5/8" X 4 1/2" annulus. Fill 4 1/2" csg with 35.5 sx cement

Name of Plugging Contractor Haliburton Services License No. 5287

Address 1102 E. 8th Street Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vintage Petroleum, Inc.

STATE OF _____ COUNTY OF _____, ss.

Rebecca Sanford (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) _____

(Address) 4200 One Williams Center
Tulsa, OK 74172

SUBSCRIBED AND SWORN TO before me this _____ day of _____

Notary Public _____

My Commission Expires: _____

USE ONLY ONE SIDE OF EACH FORM

RECEIVED
STATE CORPORATION COMMISSION
SEP 23 1993
CONSERVATION DIVISION
Wichita, Kansas
Revised 05-88