

15-063-20752-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2418  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER SPCD 3-22-1984  
LEASE NAME Flax J  
WELL NUMBER 1

RECEIVED

APR 21 2003

KCC WICHITA

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Comm. Div.  
office within 30 days

~~1360~~ 1320 Ft. from S Section Line  
660' Ft. from E Section Line  
Sec. 24 TWP. 15 S RGE. 26 W (E) or (W)  
COUNTY Gove  
Date Well Completed 1984  
Plugging Commenced 4-3-2003  
Plugging Completed 4-4-2003

LEASE OPERATOR MICA Energy Corp  
ADDRESS P.O. Box 20707, Oklahoma City, OK 73156  
PHONE # (405) 942-4552 Operator License # 32047

Character of Well Dry  
(Oil, Gas, O&G, SWD, input, Water Supply Well)

The plugging proposal was approved on April 2, 2003 by Herb Deines (date)  
by District Coordinator-Hays, KS - Brad Seib, Owner Plains, Inc. (XCC District Agent's Name)

Is ACO-1 filled? Yes If not, is well log attached? No  
Producing Formation Mississippi Depth to Top 4407 Bottom 4411 T.D. 4447

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Mississippi	oil-water	4407	4411	8 5/8"	327	-0-
LKC		3980	3984	4 1/2"	cemented	to surface

Describe in detail the manner in which the well was plugged. Indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

See detailed report on back of page

Name of Plugging Contractor Plains, Inc. License No. KLN 4072  
Address Box 346, Ness City, KS 67560-0346

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: MICA Energy Corp.  
STATE OF Oklahoma COUNTY OF Oklahoma, ss.

(Employee of Operator) or (Operator) of  
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) [Signature]  
(Address) P.O. Box 20707, Okla. City, OK 73156

SUBSCRIBED AND SWORN TO before me on this 17th day of April, 2003  
[Signature] 01016608  
Notary Public

My Commission Expires: Oct. 2, 2005

[Signature]

Flax J #1--Plugging of well.

4/3/03 MIRU - Unseated pump. Laid down 174 - 3/4" rods. RU to pull tubing. Pulled - changed head for working head. Talled tubing. Back in hole to 4403' Shut-down for day.

4/4/03 Mixed 35 sacks cement with 400 # hulls. Pumped down to 4400'. Pulled tubing to 3500'. Mixed 14 sacks gel spacer circulated to 1900'. Pulled tubing to 1920'. Mixed 50 sacks cement and circulate to surface. Pulled tubing out of hole. Hooked up to 4 1/2" casing. Mixed 15 sacks cement pump down casing. Pressure tested to 400#. Hooked up to braden head. Pumped 25 sacks down . annulus. Pressure to 300#. Rigged down. Job complete.