

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-22065-00-00  
Spot: NESENW Sec/Twnshp/Rge: 20-16S-13W  
3630 feet from S Section Line, 2310 feet from W Section Line  
Lease Name: STOSKOPF Well #: 8  
County: BARTON Total Vertical Depth: 3412 feet

Operator License No.: 34506  
Op Name: EMPIRE ENERGY E&P, LLC  
Address: 345 RIVERVIEW ST., STE 540  
WICHITA, KS 67203

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3411		125 SX
SURF	8.625	255		225 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/13/2015 11:00 AM  
Plug Co. License No.: 30891 Plug Co. Name: LEIKER WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD LACEY Company: EMPIRE ENERGY E&P Phone: (620) 617-0603

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
Casing parted at 700'. Tried to get past part. Drilled and milled for 3 days and could not get past part.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/13/2015 11:00 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 365'. Ran tubing to 690' and pumped 160 sx cement. Circulated cement to surface on casing. Closed valve on casing and circulated cement up surface with 60 sx cement. Pulled tubing. Tied to casing and topped off with 10 sx cement. Pushed cement back up surface with 55 sx cement.

GPS: 38.64783 -098.78539

Perfs:

Top	Bot	Thru	Comments
3342	3346		
3316	3320		
3276	3280		
3206	3210		
3170	3176		
3146	3150		
3075	3080		
3000	3004		
2932	2935		
2822	2826		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

4/1/15 CKM

District: 04

Signed Bruce Rodie  
(TECHNICIAN) CR

KCC WICHITA

MAR 30 2015

RECEIVED

Form CP-2/3

MAR 19 2015