

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-01213-00-01
Spot: NESWNWSW Sec/Twnshp/Rge: 19-20S-13W
1651 feet from S Section Line, 4927 feet from E Section Line
Lease Name: PANNING Well #: 2-19 SWD
County: BARTON Total Vertical Depth: 3800 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3607		200 SX
SURF	8.625	252		80 SX

Well Type: SWD UIC Docket No: D31259.0 Date/Time to Plug: 03/12/2015 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: SHANE PELTON Company: HERMAN LOEB Phone: (719) 340-8987

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 15 sx gel and 500 # hulls.
Well has a port collar at 802' and cement was circulated to surface with 350 sx cement.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/12/2015 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1300'. Ran tubing to 3590' and pumped 60 sx cement w/150 # hulls. Pulled tubing to 3090' and pumped 15 sx gel. Pulled tubing to 1476' and pumped 60 sx cement w/100 # hulls. Pulled tubing to 812'. Circulated cement to surface with 120 sx cement. Pulled tubing and topped off with 75 sx cement.

GPS: 38.29448 -098.81013

Perfs:

Top	Bot	Thru	Comments
3607	3800		

Remarks: ALLIED CEMENTING

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

KCC WICHITA

MAR 30 2015

RECEIVED

Form CP-2/3

MAR 19 2015

cc:ule

4/1/15 CKM