

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-25655-00-00
Spot: S2NENWSW Sec/Twnshp/Rge: 19-20S-13W
2306 feet from S Section Line, 990 feet from W Section Line
Lease Name: PANNING Well #: 1-19
County: BARTON Total Vertical Depth: 3600 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3591		85 SX
SURF	8.625	792		400 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/11/2015 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: SHANE PELTON Company: HERMAN LOEB Phone: (719) 340-8987

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 15 sx gel and 500 # hulls. Well has port collar at 2729' with 385 sx cement. Top of cement at 1600'.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/11/2015 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1300' and 780'. Ran tubing to 3466' and pumped 15 sx gel followed by 60 sx cement w/100 # hulls. Pulled tubing to 1467' and pumped 65 sx cement w/100 # hulls. Pulled tubing to 812'. Circulated cement to surface with 100 sx cement and 50 # hulls. Pulled tubing. Topped off with 15 sx cement pressured to 400 psi. Tried to pumped into surface pipe and it pressured up.

GPS: 38.29627 -098.80777

Perfs:

Top	Bot	Thru	Comments
3542	3546		
3533	3536		
3526	3529		
3514	3558		
3342	3346		
3286	3295		
3266	3272		

Remarks: ALLIED CEMENTING

Plugged through: TBC
ESG

4/1/15 CKM

District: 04

Signed Bruce Rodie
(TECHNICIAN) CM

KCC WICHITA

Form CP-2/3

MAR 19 2015

MAR 30 2015

RECEIVED