

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-097-21786-00-00
Spot: NWSEWNWNE Sec/Twnshp/Rge: 19-27S-18W
985 feet from N Section Line, 1660 feet from E Section Line
Lease Name: RANDEL Well #: 1-19
County: KIOWA Total Vertical Depth: 4920 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4370		WITH 2 SX CMT
CIBP		4750		
PROD	5.5	4918	1996	WITH 200 SX CMT
SURF	8.625	605		WITH 350 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/13/2015 12:00 PM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: MIKE POLLEY Company: HERMAN L. LOEB, LLC Phone: (719) 342-5600

Proposed Plugging Method: SET CIBP @ 4370' WITH 2 SX CMT. PLUG AT 1240' WITH 20 SX GEL & 50 SX CMT. PLUG AT 640' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 03/13/2015 5:15 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4370' WITH 2 SX CMT. 1ST PLUG AT 1236' WITH 20 SX GEL & 50 SX CMT. 2ND PLUG AT 644' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4790	4804		
4778	4787		
4413	4418		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

4/1/15 CKM

District: 01

Signed [Signature]

RECEIVED
MAR 25 2015
KCC DODGE CITY

(TECHNICIAN)
Received
KANSAS CORPORATION COMMISSION

MAR 30 2015

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3