

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-053-21275-00-00
Spot: NESWSE Sec/Twship/Rge: 19-15S-10W
710 feet from S Section Line, 1650 feet from E Section Line
Lease Name: BRANDA A Well #: 1
County: ELLSWORTH Total Vertical Depth: 3334 feet

Operator License No.: 31203
Op Name: MCQUADE, OWEN DBA OWEN'S PUMP
Address: 640 E SUNSET AVE
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2920		
CIBP	5.5	3260		
PROD	5.5	3327	2355	160 SX
SURF	8.625	432		225 SX
T1	2.875	3250		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/11/2015 10:30 AM
Plug Co. License No.: 33385 Plug Co. Name: J & M WELL SERVICING, INC.
Proposal Rcvd. from: OWEN MCQUADE Company: MCQUADE, OWEN Phone: (785) 483-6321

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 02/20/2015 2:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SET CIBP AT 3260' AND CAP WITH 2 SX'S CEMENT. SET CIBP AT 2920' AND CAP WITH 2 SX'S CEMENT. QUALITY WELL SERVICE RIGGED UP ON 2-20-15, AND CASING WAS SHOT OFF AT 2355' AND PULLED TO 1300' WHERE 35 SX'S CEMENT WITH 2% CC WAS PUMPED. PULL CASING TO 1000'. WAIT 1.5 HRS AND TAG CEMENT WITH SAND-LINE @ 1172'. PUMP 35 SX'S CEMENT @ 1000'. PULL CASING TO 482' AND CIRCULATE 140 SX'S CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF. USED 210 SX'S CEMENT.

Perfs:

Top	Bot	Thru	Comments
3284	3287	CSG	
2963	2966	CSG	
2935	2938	CSG	

Remarks: 60-40 POZ, 4% GEL. EXCEL PERF-SHOOT OFF #0755. L.K. WIRELINE #14464 FOR SETTING CIBPS. QUALITY CEMENT #6009.

Plugged through: CSG

Received
STATE CORPORATION COMMISSION

4/11/15CKM

District: 02

MAR 30 2015
CONSERVATION DIVISION
WICHITA, KS

Signed

Virgil Clothier
(TECHNICIAN)