

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-22602-00-00  
Spot: NENWNE Sec/Twnshp/Rge: 8-20S-12W  
4950 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: SCHARTZ Well #: 8-4  
County: BARTON Total Vertical Depth: 3512 feet

Operator License No.: 31528  
Op Name: MIKE KELSO OIL, INC.  
Address: PO BOX 467  
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3500	1888	150 SX
SURF	8.625	300		300 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/27/2015 1:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/27/2015 4:00 PM KCC Agent: BRUCE RODIE

**Actual Plugging Report:**

Sanded off perforations and topped with cement. Cut casing at 1888'. Pulled casing to 1420' and pumped 125 sx cement w/200 # hulls. Pulled casing to 900' and pumped 50 sx cement w/100 # hulls. Pulled casing to 600' and pumped 50 sx cement w/100 # hulls. Pulled casing to 300'. Circulated cement to surface w/80 sx cement. Pulled casing and hole stayed full.

GPS: 38.33255 -098.67014

**Perfs:**

Top	Bot	Thru	Comments
3483	3485		
3473	3478		
3460	3462		
3448	3451		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

4/1/15 CKM

CM

KCC WICHITA

MAR 30 2015

RECEIVED

MAR 06 2015

Form CP-2/3