

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-20218-00-00
Spot: N2S2SWNW Sec/Twnshp/Rge: 23-14S-28W
3150 feet from S Section Line, 4620 feet from E Section Line
Lease Name: COBBEE UNIT Well #: 2-A1
County: GOVE Total Vertical Depth: 4185 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4000		
PROD	4.5	4175		170 SX
SURF	8.625	329		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/16/2015 8:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 550 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Shot perforations at 1985', 1035' and 320'.
Perforations at 3903' - 3906', 3940' - 3946' and 3997' - 4000'.
CIBP at 4000'

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/16/2015 1:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3919' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 3328' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 2425' and pumped 290 sx cement. Good circulation of cement out of casing and backside. Pulled tubing out and topped off casing with 30 sx cement.

Perfs:


Top	Bot	Thru	Comments
4111	4115		
4102	4104		
4086	4089		
3997	4000		
3940	3946		
3903	3906		

Remarks: SWIFT CEMENT TICKET # 27148

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

4/1/15

CM

KCC WICHITA

Form CP-2/3

MAR 19 2015

MAR 30 2015

RECEIVED