

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-21069-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 22-14S-28W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease Name: COBBEE UNIT Well #: 1-1
County: GOVE Total Vertical Depth: 4250 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4244		440 SX
SURF	8.625	381		240 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/10/2015 8:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 375 sx 60/40 pozmix 4% gel cement w/400 # hulls and 12 sx gel.
DV Tool at 2054' w/260 sx cement.
Perforations at 4121' - 4123', 4143' - 4144' and 4147' - 4150'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/10/2015 11:15 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4166' and pumped 12 sx gel followed by 50 sx cement w/150 # hulls. Pulled tubing to 2216' and pumped 160 sx cement w/150 # hulls. Good circulation of cement. Pulled tubing out and topped off casing w/25 sx cement full. Tied on to backside and it was full of cement.
GPS: 38.82111 -100.41814


Perfs:

Top	Bot	Thru	Comments
4147	4150		
4143	4144		
4121	4123		

Remarks: SWIFT CEMENT TICKET # 27054

Plugged through: TBG

District: 04

Signed 
(TECHNICIAN)

4/1/15CKM

CM

MAR 16 2015

KCC WICHITA

MAR 30 2015

RECEIVED