

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-063-21112-00-00  
Spot: NWNESE Sec/Twnshp/Rge: 22-14S-28W  
2310 feet from S Section Line, 990 feet from E Section Line  
Lease Name: COBBEE UNIT Well #: 1-2  
County: GOVE Total Vertical Depth: 4350 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4316		180 SX
SURF	8.625	427		240 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/11/2015 11:30 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 375 sx 60/40 pozmix 4% gel cement w/400 # hulls and 12 sx gel.  
DV Tool at 2011' w/260 sx cement.  
Perforations: 4110' - 4113' and 4136' - 4140'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/11/2015 2:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4130' and pumped 12 sx gel followed by 60 sx cement w/150 # hulls. Pulled tubing to 2188' and pumped 200 sx cement w/150 # hulls. Good circulation of cement. Pulled tubing out and topped off w/40 sx cement. Tied on to backside and squeezed w/5 sx cement. Shut in pressure 200 psi.

GPS: 38.82115 -100.41361

Perfs:


Top	Bot	Thru	Comments
4136	4140		
4110	4113		

Remarks: SWIFT CEMENT TICKET # 28300

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

4/1/15 CKM

MAR 16 2015

KCC WICHITA

MAR 30 2015

RECEIVED