

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-21137-00-00
Spot: SEWSE Sec/Twnshp/Rge: 22-14S-28W
1650 feet from S Section Line, 1650 feet from E Section Line
Lease Name: COBBEE UNIT Well #: 1-3
County: GOVE Total Vertical Depth: 4210 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4188		180 SX
SURF	8.625	321		240 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/12/2015 1:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 375 sx 60/40 pozmix 4% gel cement w/400 # hulls.
Perforations at 3966' - 3972', 3996' - 4000'.
DV Tool at 2027' w/250 sx cement.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/12/2015 4:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3962' and pumped 65 sx cement w/150 # hulls. Pulled tubing to 3127' and pumped 75 sx cement w/150 # hulls. Pulled tubing to 2106' and pumped 225 sx cement w/200 # hulls. Good circulation of cement. Pulled tubing out and topped off with 45 sx cement full. Tied on to backside and squeezed with 15 sx cement. Shut in pressure 300 psi.

GPS: 38.81936 -100.41595

Perfs:

Top	Bot	Thru	Comments
3996	4000		
3966	3972		

Remarks: SWIFT CEMENT TICKET # 27056

Plugged through: TBG

District: 04

Signed _____

(Signature)
(TECHNICIAN)

4/1/15 CKM

CM

KCC WICHITA

MAR 30 2015

RECEIVED

MAR 16 2015