

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-097-20783-00-02
Spot: SWNESW Sec/Twnshp/Rge: 1-28S-18W
1676 feet from S Section Line, 3665 feet from E Section Line
Lease Name: KIRK Well #: 4
County: KIOWA Total Vertical Depth: 4925 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1200		
CIBP		4200		
PROD	4.5	4859	0	WITH 350 SX CMT
SURF	8.625	336		WITH 250 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/10/2015 9:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: STAN FROETSCHNER Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: SQUEEZE PERFS WITH 20 SX CMT & HULLS. SET CIBP @ 1200'. LOAD & TEST. IF OKAY, PERFORATE AT 1140' & SPOT 50 SX CMT WITH HULLS IN LAST 25 SX CMT. PERFORATE AT 350' & CIRCULATE CMT TO 0'.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: PARTIAL
Date/Time Plugging Completed: 03/10/2015 4:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

THROUGH TBG AT 3520' PUMPED 20 SX CMT WITH 50# HULLS. PULLED TBG & SET CIBP @ 1200'. LOADED THE CASING & PRESSURED TO 300#. PERFORATED AT 1140' & PUMPED 50 SX CMT WITH 100# HULLS IN THE LAST 25 SX CMT. PERFORATED AT 350' & CIRCULATED CMT TO SURFACE WITH 130 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4365	4372		
4342	4348		
4204	4213		
4178	4182		
3506	3509		

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

4/1/15 ckm

District: 01

RECEIVED
MAR 25 2015
KCC DODGE CITY

Signed Eric MacLaren
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

MAR 30 2015

CONSERVATION DIVISION
WICHITA, KS