

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-057-20719-00-01
Spot: SWNE Sec/Twnshp/Rge: 9-28S-22W
2699 feet from N Section Line, 2113 feet from E Section Line
Lease Name: MAUPIN-FISHER Well #: 1
County: FORD Total Vertical Depth: 5208 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		1390		WITH 240 SX CMT
PROD	4.5	5204	0	WITH 200 SX CMT
SURF	8.625	343		WITH 425 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/18/2015 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: GARY ROWE Company: RITCHIE EXPLORATION Phone: (620) 214-0300

Proposed Plugging Method: ESTABLISH PUMP RATE THROUGH PERFS, IF GOOD PUMP 30 SX CMT WITH 250# HULLSM MUD SPACER TO ANHYDRITE & CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/18/2015 11:00 AM KCC Agent: LARRY HARRIS

Actual Plugging Report:

LOADED HOLE 3 BBL PER MINUTE, PUMPED 2/3 BBL PER MINUTE THROUGH PERFS ESTABLISHING PUMP RATE. PUMPED 30 SX CMT WITH 200# HULLS, PUMPED 52 SX GEL SPACER TO 1400'. PUMPED 65 SX CMT TO SURFACE. HELD AT 800 PSI.

Perfs:

Top	Bot	Thru	Comments
5096	5099		
5027	5031		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed Larry Harris (TECHNICIAN)

4/1/15 ckm

JA

RECEIVED
MAR 25 2015
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

MAR 30 2015

CONSERVATION DIVISION
WICHITA, KS