

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-101-20214-00-01  
Spot: NENWNE Sec/Twnshp/Rge: 2-17S-29W  
4797 feet from S Section Line, 1949 feet from E Section Line  
Lease Name: EATON Well #: 1  
County: LANE Total Vertical Depth: 4608 feet

Operator License No.: 30029  
Op Name: STANDARD OPERATING COMPANY  
Address: 1000 N TYLER STE 100  
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4526		
DVT		2183		
PROD	5.5	4565	0	WITH 200 SX CMT
SURF	8.625	280		175 SX

Well Type: EOR UIC Docket No: E19404.2 Date/Time to Plug: 03/10/2015 10:00 AM  
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.  
Proposal Rcvd. from: HAL HOSS Company: CHEYENNE WELL SERVICE, INC. Phone: (785) 798-2282

Proposed Plugging Method: SPOT SAND 50' ABOVE PERFS WITH 5 SX CMT. RUN TBG TO 2200'. CIRCULATE CMT TO SURFACE. PULL TBG. TOP OFF WITH 50 SX CMT. FILL BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/10/2015 11:30 AM KCC Agent: LARRY HARRIS

Actual Plugging Report:

SANDED BACK PERFS TO 4050' WITH 5 SX CMT. PUMPED 15 SX CMT DOWN BACKSIDE. HELD PRESSURE AT 300 PSI. RAN TBG IN HOLE TO 2050' & PUMPED 210 SX CMT TO SURFACE. TOPPED OFF WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4538	4548		
4170	4175		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed

Larry A. Harris (TECHNICIAN) SA

RECEIVED  
MAR 24 2015  
KCC DODGE CITY

Received  
KANSAS CORPORATION COMMISSION

Form CP-2/3

MAR 30 2015

CONSERVATION DIVISION  
WICHITA, KS

cc:uic