

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-101-20275-00-00  
Spot: E2NENW Sec/Twnshp/Rge: 2-17S-29W  
4649 feet from S Section Line, 2950 feet from E Section Line  
Lease Name: EATON Well #: 4  
County: LANE Total Vertical Depth: 4594 feet

Operator License No.: 30029  
Op Name: STANDARD OPERATING COMPANY  
Address: 1000 N TYLER STE 100  
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4588	0	WITH 250 SX CMT
SURF	8.625	287		WITH 180 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/10/2015 12:30 PM  
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.  
Proposal Rcvd. from: HAL HOSS Company: CHEYENNE WELL SERVICE, INC. Phone: (785) 798-5051

Proposed Plugging Method: SAND 50' ABOVE PERFS WITH 5 SX CMT. RUN TBG TO 2200' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. USE 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/10/2015 2:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

SANDED BACK PERFS TO 4350' WITH 5 SX CMT. PUMPED 20 SX CMT BACKSIDE. HELD PRESSURE AT 300 PSI. RAN TBG TO 2200' & PUMPED 190 SX CMT TO SURFACE. LOST CIRCULATION. SHUT DOWN. 3/13/15: TAGGED CMT AT 900' & TOPPED OFF WITH 65 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4552	4556		
4546	4549		
4479	4485		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed Larry D Harris (TECHNICIAN)

RECEIVED  
MAR 26 2015  
KCC DODGE CITY

Received  
KANSAS CORPORATION COMMISSION

Form CP-2/3

MAR 30 2015

CONSERVATION DIVISION  
WICHITA, KS