

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-079-00642-00-01
Spot: SWNESE Sec/Twnshp/Rge: 14-22S-2W
1650 feet from S Section Line, 990 feet from E Section Line
Lease Name: C BACHMAN Well #: 1
County: HARVEY Total Vertical Depth: 3374 feet

Operator License No.: 5822
Op Name: VAL ENERGY, INC.
Address: 125 N MARKET ST STE 1710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PKR	0	3173		
PROD	5.5	4716		100 SX
SURF	8.625	257		125 SX
T1	2.375	3173		

Well Type: EOR UIC Docket No: E04552.1 Date/Time to Plug: 03/09/2015 12:00 AM
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.
Proposal Rcvd. from: DEON HOWARD Company: VAL ENERGY Phone: (316) 263-6688

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE
Date/Time Plugging Completed: 03/09/2015 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SET CIBP @ 3270' CAPPED WITH 2 SX CEMENT ON TOP. CUT HEAD OFF. WIRE LINE PERF @ 400' WITH 4 SHOTS. PUMPED 150 SX CEMENT AT 300 LBS TO CIRCUALTE AROUND 5.5" CASING. FELL BACK 150' INSIDE CASING, 4' BETWEEN CASING AND SURFACE. ADDED ANOTHER 30 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
3314	3370		

Remarks: QUALITY WELL SERVICE PROVIDED CEMENT AND PUMP TRUCKS TO COMPLETE THIS JOB, CLASS A COMMON CEMENT USED. FAILED MIT; WITH HOLES IN CASING.

Plugged through: CSG

4/1/15 CKM

District: 02

Received
KANSAS CORPORATION COMMISSION

Signed

BJ Hope

(TECHNICIAN)

MAR 30 2015

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

1/8

CC:UIC