

6-100460

9-26

12/R

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-063-21,439-00.00

S2 NW SE /4 SEC. 19, 15 S, 28 W  
1560 feet from S section line  
2100 feet from E section line

Operator license# 4782

Lease Coberly Partnership well # 1-19

Operator: Ensign Operating Comp.

County Gove

Address: 621 17th Street  
Suite 1800  
Denver, Colo. 80293

Well total depth 4350 feet <sup>141.38</sup>  
Conductor Pipe:        inch @        feet  
Surface pipe 8 5/8 Inch @ 227 feet

Aband. oil well       , Gas well       , Input well       , SWD       , D & A X

Plugging contractor: Murfin Drilling Co., Inc. License# 30606

Address: Wichita, Kansas 67202

Company to plug at: Hour: ?? Day:        Month:        Year:       

Plugging proposal received from: Herb Brady

Company: Murfin Drilling Co. phone:       

Were: **Spot plugs through drill pipe w/ heavy mud between all plugs.**

1st plug @ 1825 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 865 feet " 100 " Mousehole:        sacks

3rd plug @ 275 feet " 40 "

4th plug @ 40 feet " Wiper plug & 10 sx.

5th plug @        feet "

Plugging Proposal Received by: David K. Wann

Plugging operations attended by agent? All[        ], Part[        ], None[ X ]

Completed: Hour: 7:30 pm, Day: 26, Month: September, Year: 1992

Actual plugging report: Hole reported plugged as above.

Order 190 sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Elevation: 2464 GL, Anhydrite depth: 1886 -        feet

Anhy. plug: YES Dakota plug: YES Bottom hole plug in place: NO

Plugged through drill pipe: YES

Did NOT penetrate Arbuckle, cemented by Allied

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 25 1992

I did        / did not [X] observe the plugging.

David K. Wann  
David K. Wann P.I.R.T. II  
(agent)

DATE 12-4-92

INV. NO. 36974