

6 031084

4-22-88

API NUMBER 15-

063-21,191-00-00

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION NE NE SW , SEC. 20 , T 15 S, R 30 W/E  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

2310 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393

Lease Name Roemer Well # 1

Operator: Abercrombie Drilling Inc.  
Name & Address: 801 Union Center  
Wichita, Ks. 67202

County Gove 143.52  
Well Total Depth 4416 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 347

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ U&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Abercrombie Drilling Inc. License Number 5422

Address Wichita, Ks.

Company to plug at: Hour: AM Day: 22 Month: April Year: 19 88

Plugging proposal received from W. Dreiling

(company name) Abercrombie (phone) \_\_\_\_\_

were: 8 5/8" set at 347' w/210 sks cwc. Circulate hole w/no less than 36 vis.  
mud w/ no loos or gain of total fluids. Spot cement plugs w/drill pipe.  
Balance plugs w/mud. Order 190 sks 60/40 Poz 6% Gel 3% CC 8 5/8" wiper plug.  
Allied Cement Co.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 9:15AM Day: 22 Month: April Year: 19 88

ACTUAL PLUGGING REPORT Spot plugs at 2075' w/25 sks

1000' w/100 sks and 1 sk Hulls

400' w/40 sks

40' w/10 sks

RECEIVED  
STATE CORPORATION COMMISSION

Circ 15 sks in rat hole w/joint of pipe

MAY 17 1988

5-17-88

Remarks: Elev 2640' GL Anhy 2066' - 97

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-19-88

INV. NO. 20743

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow