

4-041979

5-30

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-063-21,521-00-00
SE SE NW /4 SEC. 35, 15 S, 30 W
2970 feet from S section line
2970 feet from E section line

RECEIVED

JUL 21 1998

Operator license# 5003

Lease: Lewis "G" Well # 1-35

Operator: McCoy Petroleum Corporation

County: Gove

Address: 3017 N. Cypress
Wichita, Kansas 67226

Well total depth 4425 ^{143.82} feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 228 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Mallard J.V. Inc. License# 4958

Address:

Company to plug at: Hour: P.M. Day: 30 Month: May Year: 1998

Plugging proposal received from: Carol Nickel

Company: Mallard J.V., Inc. Phone:

Were: Order 200 sxs 60/40 posmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour 3:00 P.M., Day: 30 Month: May, Year: 1998

Actual plugging report:

- 1st. Plug at 2075' w/25 sxs.
- 2nd. Plug at 1085' w/100 sxs.
- 3rd. Plug at 280' w/40 sxs.
- 4th. Plug at 40' w/10 sxs.

Rathole with 15 sxs.

Mousehole with 10 sxs.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: 2663 GL

I did [] / did not [X] observe the plugging.

Dennis J. Hamel
(agent)

Form CP-2/3

INVOICED

DATE JUL 22 1998

INV. NO. 50966