

10 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

APR 1 1963

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Skelly Oil Company

Complete Address: 1020 North Main Hutchinson, Kansas

Lease Name Charles Merkle Well No. # 1

Location App. C-NW Sec. 15 Twp. 34 Rge. 27 (E) (W)

County Meade Total Depth 6090'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Ace Pipe Pulling Company

Address: Great Bend, Kansas License No. # 2

Operation Completed: Hour 1 PM Day 29 Month 3 Year 63

The Above well was plugged as follows:

<u>8 5/8" 1386' Circulated w/cement.</u>	<u>4 1/2" 4801' Cemented</u>
<u>Plug back to 4760'</u>	<u>Top perforations 4727'</u>
<u>Sand 4760' to 4700'</u>	<u>2 Sax.cement 4700' to 4676'</u>
<u>Mud 4676' to 710'</u>	<u>Rock bridge 710' to 700'</u>
<u>35 Sax.cement 700' to 600'</u>	<u>Mud 600' to 50'</u>
<u>Rock bridge 50' to 40'</u>	<u>15 sax.cement 40' to surface.</u>
<u>Weld. plate on surface.</u>	<u>Company Pump. Pulled 4140' 4 1/2" Pipe.</u>

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Blugh Scott
Well Plugging Supervisor

DATE 4/1/63
INV. NO. 6806-u