

10 KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

SEP 10 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Graham-Michaelis Drilling Company

Complete Address: 211 North Broadway, Wichita, Kansas

Lease Name Riemer Well No. 1-13

Location 1250' FSL & 660' FWL Sec. 13 Twp. 34S Rge. 27 (E) (W)

County Meade Total Depth 6218'

Abandoned Oil Well      Gas Well  Input Well      SWD Well      D & A

Other well as hereafter indicated:     

Plugging Contractor: Sargent Casing Pulling Service

Address: Liberal, Kansas License No. 511

Operation Completed: Hour 7 PM Day 7 Month 9 Year 63

The Above well was plugged as follows:

8 5/8"-1327' Circulated w/cement. 4 1/2"-6214' Cemented.

Perforations - 6015'-6030'-5984'

Mud 6213' to 5984' 15 Sax.cement 5984' to 5804'

Mud 5804' to 700' 35 Sax.cement 700' to 600'

Mud 600' to 50' Bridge 50' to 40'

15 Sax.cement 40' to surface. Cut surface off 3' below ground level.

Weld plate on surface. Company Pump. Pulled 2797' 4 1/2" Pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Hugh Scott  
Well Plugging Supervisor

DATE 9/10/63

INV. NO. 9925-W