

KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING SUPERVISOR'S REPORT

R

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 104-14 Location: E W 1/2
County: Meade Sec. 12 Twp. 34 Rge. 26 (E) (W)
Name of Field or Pool: McKinney Total Depth: 5830

I have this date completed supervision of plugging of:

Well No. 1 Lease Theis "A"
Operator's Full Name Graham-McKaslin Drilling Co

Complete Address: 211 N Broadway Wichita Kansas

Plugging Contractor: Southwest Casings Pulling Co

Address: Great Bend Kansas License No. 399

Abandoned Oil Well Gas Well Input Well SWD Well D & A

If well is a rotary drilled dry hole did operators wait for you to arrive _____

If yes how long _____ Reason: _____

Operation Completed: Hour 11^{am} Day 15 Month June Year 1958

The above well was plugged as follows:

8 1/2" S.P. 1157' P.W.C. 5 1/2" 5829' cement 1500x Reamed 4500'
hole drilled with sand to 5660' Dumped 5x cement
Pumped 144 BBLs Very light mud through 5 1/2" at 2000'
With water truck. Pump. This mud not approved by me.
Bailed hole to 550' After pulling 5 1/2" set Plug 550' dumped
20x cement Mud heavy clay to face of collar.

I hereby certify that the above well was plugged as herein stated and that I was present while the above well was being plugged.

Signed: M. L. Rivers
Well Plugging Supervisor

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

This hole is not plugged from 1150' down with heavy
enough mud to prevent up or down migration of
any inferior water. to the best of my knowledge.

Reviewed: J. Lewis Brock
Field Supervisor

Signed: _____
STATE CORPORATION COMMISSION
Well Plugging Supervisor

Remarks:

PLUGGING
FILE SEC 12 T 34 R 26
BOOK PAGE 104 LINE 14

RECEIVED
JUN 24 1958
CONSERVATION DIVISION
Wichita, Kansas