

15-119-00042-0000

Form CP-3
Rev. 6-26-62

af
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
SEP 9 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Graham-Michaelis Drilling Co.

Complete Address: Box 1294, Liberal, Kansas 67901

Lease Name Florence Walker Well No. 1

Location SW SW NE Sec. 35 Twp. 34 Rge. 26 ~~34~~ (W)

County Meade Total Depth 6111'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Sargents Casing Pulling Co.

Address: Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 4:00PM Day 5 Month 9 Year 1968

The Above well was plugged as follows:

8 5/8" to 1228' circulated w/ cement. 5 1/2" to 6110' cemented.

Top perforations 5907' Plug bottom w/ 25 sacks cement.

Top of cement 5400' Mud 5400' to 700'

Spotted 35 sacks cement 700' to 600' Mud 600' to 45'

Plug, hulls & 15 sacks cement 45' to 0'. Company Pump.

Pulled 2817' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: Edgar J. Eves
Well Plugging Supervisor

INVOICED

DATE 9/9/68

INV. NO. 8434-W