

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 7 1967
3-7-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Texaco, Inc.

Complete Address: 614 Bittig Bldg., Wichita, Kansas

Lease Name H. G. Adams Well No. 1

Location C NE Sec. 27 Twp. 34 Rge. 29 (E) (W)

County Meade Total Depth 3345'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Sargents Casing Pulling

Address: Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 3:30 Pm Day 4 Month 3 Year 1967

The Above well was plugged as follows:

13 3/8" to 40' circulated w/ cement. 8 5/8" to 444' circulated w/ cement .

2 7/8" to 3343' cemented. Top Pefforations 3263'

Plug bottom w/ 5 sacks cement, Top of cement 3100'

Mud 3100' to 450' Spotted 40 sacks cement 450' to 350'

Mud 350' to 45' Plug, Halls & 15 sacks cement 45' to 0'

Company Pump. Pulled 2611' of 2 7/8" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edgar J. Lores
Well Plugging Supervisor

DATE 3/7/67
INV. NO. 4877-W