

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20815-00-01
Spot: NESWNE Sec/Twnshp/Rge: 6-34S-27W
3730 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: DAVIS Well Number: 1-6
County: MEADE Total Vertical Depth: 6087 feet

Operator License No.: 4247 Conductor Pipe: Size feet: 8197.83
Op Name: DOLOMITE RESOURCES CORPORATION Surface Casing: Size 8.625 feet: 603 WITH 375 SX CMT
Address: 2250 N. ROCK ROAD Production: Size 4.5 feet: 5934
WICHITA, KS 67226 Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 01/14/2002 11:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Revd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PUMP 200# HULLS & 20 SX CMT. PLUG AT 1250' WITH 50 SX CMT. PLUG AT 640' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 01/14/2002 3:00 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 6010'. PERFS AT 5964-5980'. PUMP 200# HULLS & 20 SX CMT. LOAD HOLE WITH MUD. 1ST PLUG PULL TO 1250' & SPOT 50 SX CMT. 2ND PLUG PULL TO 640' & SPOT 50 SX CMT. 3RD PLUG PULL TO 40' & CIRCULATE CMT TO SURFACE. STAYED FULL.

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2610' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed [Signature]

(TECHNICIAN)

RECEIVED

1-25-02
JAN 25 2002

KSG WICHITA

INVOICED JAN 18 2002

DATE Jan 25, 02 MP

INV. NO. 2002061316

Form 223